

BIM MANAGEMENT & COORDINATION SERVICES

Technical proposal · Execution methodology · Financial offer

PROJECT	Kampala Uganda Temple Project
PREPARED FOR	Symbion Consulting Group Studios
ATTENTION	Ronald Katabira MCIOB, Director
PREPARED BY	Mayanja Davis CAD BIM Specialist
CONTACT	mayanjadavis@gmail.com · +256 787 472 999
DATE	17 June 2026
REFERENCE	DV-BIM-PRO-001 v3

This proposal is confidential and is submitted for the sole use of Symbion Consulting Group Studios in evaluating BIM management services for the above project. Fees are valid for 30 days from the date above. This revision supersedes previous versions, aligns the programme and fee to the Owner's revised Work Program (June 2026), and adopts only the platforms the Owner provides.

Contents

Executive summary	3
1. Project understanding	3
1.1 The development	3
1.2 The delivery framework	4
1.3 The BIM Manager role	4
2. Scope of services.....	4
2.1 Services included	4
2.2 Services excluded	5
3. Proposed BIM environment.....	6
3.1 The Owner-mandated environment, adopted as found	6
3.2 The two items the documents leave open	7
3.3 Information hierarchy: one source of truth per information type	8
3.4 Standards and naming	8
3.5 Unified LOD matrix	8
3.6 Model breakdown structure	9
3.7 Hardware and connectivity requirements	10
3.8 Fohlio as the asset-data backbone	10
3.9 Requirements traceability	11
4. Execution methodology.....	12
4.1 Stage 0: mobilisation (months 1 to 2)	12
4.2 Stage 1: design coordination (Phase 2, months 1 to 11)	12
4.3 Stage 2: construction (Phase 3, 32 months)	12
4.4 Stage 3: close-out and Deliverable D (within 60 days of furniture installation)	13
4.5 Meetings and reporting cadence	13
4.6 Key performance indicators.....	13
5. Programme and resourcing	13
6. Financial proposal	14
6.1 Services fee	14
6.2 Software (optional, at cost)	15
6.3 Hardware (optional, one-off)	15
6.4 Deliverable D at LOD 500.....	15
6.5 Rates for extension and additional services	16
6.6 Payment terms.....	16
7. Commercial terms and basis.....	16
8. Acceptance.....	17

Executive summary

Symbion Consulting Group Studios requires BIM Manager coordination services for the Kampala Uganda Temple Project: six buildings totalling approximately 6,597 m² on a six acre site in Kampala's central business district, delivered over the Owner's revised Work Program of 11 months documentation and 38 months construction administration (32 months building supervision, 4 months furniture supervision and a 2 month LOD 500 close-out), ending in the Deliverable D record model.

The challenge in this engagement is not modelling; it is keeping eight or more design disciplines, two scope frameworks (the Owner's A1 phases and the engineering A2 phases), and later a contractor, exchanging accurate models against one calendar on one platform, so that the Owner receives a verified record model, at LOD 500 per the revised Work Program, within 60 days of furniture installation.

This proposal is built strictly on the platforms the Owner provides. The Owner operates a defined delivery ecosystem: Revit as the authoring platform, an Owner project management platform for all PDF deliverables, approvals and review, Fohlio for furniture, fixtures, equipment and O&M data, RIB SpecLink for specifications, Microsoft Teams for coordination and the Niagara framework for building controls. This engagement adopts that ecosystem as found and adds no third party platform: model federation and clash detection are performed by the BIM Manager in Navisworks on a dedicated workstation, with outputs published as PDFs into the Owner's platform, and the Owner's platform itself carries document sharing, review and approval. Section 3 sets this out and a requirements traceability table in Section 3.9 maps each Owner requirement to the mechanism that delivers it.

The total services fee is USD 71,750 excluding VAT, structured around the revised Work Program: full coordination during the eight active documentation months, a reduced watching-brief rate during the three month tender period, building supervision over 32 months, furniture supervision over a further 4 months, and a separate 2 month close-out producing the LOD 500 Deliverable D, which the revised Work Program lists as a distinct Phase 3 deliverable. Software (the Autodesk AEC Collection seat the BIM Manager needs for Revit and Navisworks) and hardware (a BimBox class workstation) are listed separately as optional, itemised provisions in Section 6, since neither forms part of the Owner-provided environment carried by the other consultants.

1. Project understanding

1.1 The development

Building	Approximate gross area
Temple	2,449 m ²
Meetinghouse	1,312 m ²
Housing / ancillary building	2,554 m ²
Grounds building	93 m ²
Utility building	166 m ²
Guard house	23 m ²
Total	Approximately 6,597 m²

Concept and schematic design are complete. The temple is developed from an Owner prototype (the engineering scope references the 1-40 F prototype) with significant site adaptation, and the design team spans architecture, interior design, structural, mechanical, electrical, plumbing, fire protection, civil, architectural lighting, acoustics and building enclosure disciplines, supported by quantity surveying and Owner peer reviewers.

1.2 The delivery framework

Two scope documents govern the work. Attachment A1 (the Owner's architectural and engineering design scope) structures the project as Phase 1 leadership approvals, Phase 2 documentation with Deliverables A (Basis of Design, LOD 200), B (50% documentation, LOD 300) and C (100% documentation) plus a conformed set, and Phase 3 construction administration ending in Deliverable D, an updated Revit record model at LOD 400 reflecting as-built conditions, due within 60 days of furniture installation. Attachment A2 (the engineering scope) structures the same work as Phase 2 design development, Phase 3 zoning, Phase 4 construction documents and Phase 5 construction administration, with each engineering discipline issuing 50% coordination and 100% sets per phase and a consolidated record BIM/drawing set at the end of construction.

These two frameworks describe one project with two numbering systems and, in one instance, two LOD values for the same milestone (A1 sets Deliverable B at LOD 300 while A2 sets design development deliverables at BIM LOD 200). The Owner's revised Work Program (June 2026) supplies a third, definitive calendar, which this revision adopts: Phase 2 over 11 months (Basis of Design at LOD 200, one month; 50% Deliverable B at LOD 300, three months; 100% Deliverable C at LOD 350, four months; Tender Action, Negotiation and Award, three months; with the Conformed Set inside that window), and Phase 3 over the construction period (building supervision 32 months and FFE installation supervision, both at LOD 400) closing with Deliverable D. Reconciling all three into a single BIM milestone schedule and one LOD matrix is the first task of this engagement, and Section 3.5 does so.

1.3 The BIM Manager role

The role proposed is information management, coordination and verification: establishing the BIM environment, running the federation and clash process, auditing model quality at every contractual gate, managing the construction stage flow of as-built information, and verifying the Deliverable D record model before submission to the Owner. The revised Work Program designates Deliverable D as LOD 500; this proposal addresses that change explicitly in Section 6.3. Model authoring remains with the design consultants and the contractor; the boundary is defined precisely in Section 2.

2. Scope of services

2.1 Services included

- BIM Execution Plan (BEP): authored within the first month, implementing the Owner's BIM modeling standards and LOD definitions, and covering roles and responsibilities, the model breakdown structure in Section 3.6, the unified LOD matrix in Section 3.5, naming conventions, shared coordinates and the master and task information delivery plans (MIDP/TIDP), aligned with ISO 19650 principles.

- Common data environment: build and day to day administration of the Autodesk Construction Cloud project described in Section 3.2, including folder structure, ISO 19650 information states, access rights, publishing workflows and onboarding of every consultant and, later, the contractor.
- Federation and clash detection: a fortnightly cycle in Navisworks Manage run by the BIM Manager across all discipline models, with prioritised, grouped clash reports issued 48 hours before each coordination session, issues tracked to closure in the clash register and mirrored as PDFs on the Owner platform, and the coordination sessions chaired over Teams.
- Model quality audits and LOD verification at each contractual gate: Deliverable A, Deliverable B, Deliverable C, the conformed set, and quarterly during construction, each closed with a written compliance report Symbion can place in front of the Owner alongside the drawing deliverables.
- Unified BIM milestone schedule reconciling the A1 and A2 phase frameworks so all disciplines exchange against one calendar, maintained weekly against actual milestone dates.
- Design meeting support: attendance at the weekly design coordination meetings the engineering scope requires, with federated model views prepared for live use in those meetings, and upload of coordination materials to the Owner's project management platform immediately after each meeting as A1 requires.
- Construction stage model management: onboarding the contractor and key subcontractors to the BEP, administering the model side of submittals and requests for information (RFIs) where model relevant, and operating the progressive as-built capture protocol in Section 4.3 so as-built information accumulates monthly rather than arriving at handover.
- Record model verification: within the 60 day Deliverable D window, verification of the record model (LOD 500 per the revised Work Program) against the contractor's as-built documentation and the engineers' consolidated record sets, with element asset data, parameter and naming compliance confirmed before submission to the Owner.
- Reporting: the monthly BIM status report and key performance indicators defined in Section 4.6.
- Training and onboarding: a BEP and Owner-platform workflow induction for each consultant team at mobilisation, and a contractor induction at construction commencement.

2.2 Services excluded

The following are outside the fee in Section 6 and available as additional services at the rates stated there:

- Model authoring of any discipline, including production or upgrading of the LOD 400 record model. Authoring remains with the design consultants (who author the record model from contractor as-built documentation per A1) and the contractor; this role coordinates and verifies.
- Quantity take-off, 4D programme simulation, 5D cost modelling, energy simulation, renderings and visualisations beyond coordination views.

- Scan to BIM, point cloud surveys and laser scanning verification of as-built conditions.
- COBie or other structured asset data deliverables. A1's Deliverable D requires the LOD 400 record model, native design files and O&M documentation (the latter published through Fohlio by Interior Design); structured COBie is not required by the documents and is therefore excluded, and can be quoted separately should the Owner request it.
- Site supervision, design responsibility and code compliance checking, which remain with the design consultants and the supervising team.
- Software licences for other consultants and the contractor, each of whom provides their own authoring software per standard industry practice. The BIM Manager's own Autodesk seat is itemised in Section 6.2.

3. Proposed BIM environment

The starting point of this engagement is that the Owner has already designed most of the delivery environment, and the BIM Manager's first duty is to implement it faithfully. Section 3.1 lists the Owner's mandates exactly as the documents state them. Section 3.2 adds only the minimum the BIM Manager needs to coordinate and verify, on the BIM Manager's own machine. A new Section 3.9 sets out how Fohlio is maximised to carry the asset-data role a cloud CDE would otherwise hold. Everything that follows exists to make Owner compliance demonstrable rather than asserted.

3.1 The Owner-mandated environment, adopted as found

Owner mandate (source)	What the documents require	How this engagement complies
Autodesk Revit (A1 Deliverables A to D)	Every deliverable in both PDF and native RVT; Revit models developed for project coordination and BIM clash analysis; the final record model is an updated Revit model at LOD 400.	Revit is the sole authoring platform; every gate deliverable is published dual format (PDF + RVT); the record model is verified in Revit.
Owner project management platform (A1)	All PDF documents uploaded to the Owner's platform; materials from weekly design meetings uploaded immediately after each meeting as a single dated PDF or PPT.	The post-meeting upload is a standing BIM Manager task in the weekly cycle (Section 4.2); the Owner platform remains the authoritative home of deliverables and approvals.
Review sessions (A1 Deliverable A, peer review)	PDF deliverable sets uploaded into bookmarked, hyperlinked review sessions, administered by the design consultant or the SPD Design Manager, with full Owner access, a two week minimum review, and written responses to every comment; comments must be resolved before a phase is complete.	Review sessions are run inside the Owner's own platform; the BIM Manager prepares and uploads the bookmarked, hyperlinked PDF sets and tracks comment close-out as a KPI until the Owner confirms resolution (Sections 4.2, 4.6).
Owner BIM modeling standards and LOD definitions (A1)	LOD is defined by the Owner's own standards, in which LOD 400 constitutes as-built information.	Adopted in full upon issue and supreme over interim conventions; implemented through the unified LOD matrix (Section 3.5).

Fohlio (A1)	The Owner's specification database for all furniture, fixtures, equipment and finishes; budgets and progress reports generated from it; O&M manuals published through it at close-out.	Fohlio remains authoritative for its domain; the model links to it and never duplicates it (Sections 3.3 and 3.8).
RIB SpecLink (A2, all disciplines)	Full specifications written on the Owner required SpecLink platform.	SpecLink remains authoritative for specifications; issued sets are archived with the milestone deliverables.
Microsoft Teams (A2)	Weekly coordination meetings and unlimited virtual coordination Teams calls.	All meetings run on Teams with live federated model views shared in-call.
Niagara (A2 peer review)	Every building management system controller uses the Niagara platform.	Noted as a coordination requirement for the BMS model content and controls submittals.
Fee discipline (A1 Phase 2)	Work completed without advance Owner approval may not be compensated.	Mirrored in this engagement's own change discipline: nothing beyond the stated scope proceeds without written instruction (Section 7).

3.2 The two items the documents leave open

The documents name no Revit version and no model-coordination toolset. Following Symbion's direction to use only what the Owner provides, this engagement adds no cloud common data environment and no separate review product. The two items below are the minimum needed for the BIM Manager to perform coordination and verification, and both sit on the BIM Manager's own machine rather than as project platforms:

Item	Selection	Role	Provided by
Authoring version	Autodesk Revit 2025	Version locked project-wide at kick-off so all disciplines exchange compatible files; prevents the upgrade incompatibilities that fragment multi-year projects.	Each consultant
Federation and clash	Autodesk Navisworks Manage	Federated model and rule-based clash detection run by the BIM Manager on a dedicated workstation; clash reports and federated views published as PDFs into the Owner's platform and shared in Teams.	BIM Manager (Section 6)
Meetings	Microsoft Teams	Weekly design coordination and virtual coordination calls, as named in the engineering scope; the federated model is shared live in-call.	Owner / Symbion
Document sharing, review, approval	Owner project management platform	The authoritative home of all PDF deliverables, the bookmarked review sessions	Owner

		and Owner approvals. No parallel platform is introduced.	
FF&E, finishes, O&M, asset data	Fohlio	Maximised as the project's asset-data backbone (Section 3.9), carrying the structured equipment register that links to the model.	Owner
Specifications; controls	RIB SpecLink; Niagara	Authoritative for specifications and building controls respectively.	Owner

3.3 Information hierarchy: one source of truth per information type

Coordination breaks down when two platforms hold competing versions of the same information, so the hierarchy is explicit:

Information type	Authoritative platform	Secondary record
Models (RVT, NWD, IFC)	BIM Manager workstation, published as PDF/NWD to the Owner platform	Milestone NWD archives per gate
PDF deliverables and Owner approvals	Owner project management platform	Authoritative; no parallel copy
Review comments on deliverables	Owner project management platform	Comment close-out log maintained by the BIM Manager
Coordination issues and clashes	Clash register maintained by the BIM Manager	Fortnightly clash report PDF on the Owner platform
FF&E, finishes, O&M	Fohlio	Linked, not duplicated
Specifications	RIB SpecLink	Issued sets archived with milestone deliverables

3.4 Standards and naming

Information management follows ISO 19650-2 adapted to the Owner's BIM modeling standards, which are adopted in full upon issue and take precedence wherever they differ. Until issued, the BEP applies an ISO 19650 container naming convention of the form KUT-ZZZ-XX-XX-M3-A-0001 (project, originator, volume, level, type, discipline, number), a shared site coordinate system fixed at mobilisation from the survey, and millimetre units across all disciplines. Every model exchange carries a model suitability code, so no consultant ever builds against superseded information. Because the Owner's standards are US-authored, localising them to Ugandan practice (paper sizes, units, code references, terminology) is an explicit mobilisation task, scoped in Section 4.1 and timed in the programme.

3.5 Unified LOD matrix

The matrix below reconciles the scope documents and the revised Work Program into one ruler, applying the Owner's LOD definitions (in which LOD 400 is as-built and LOD 500 is field-

verified, fully attributed asset data). Where A1 and A2 differ at the 50% documentation milestone, the higher A1 requirement (LOD 300) governs, because Deliverable B is the Owner's contractual review gate; Deliverable D follows the revised Work Program at LOD 500:

Milestone	A1 / A2 reference	Model LOD	Verification gate
Deliverable A (Basis of Design)	A1 Phase 2 / A2 carried from SD	LOD 200	Baseline audit
Deliverable B (50% documentation)	A1 Deliverable B / A2 design development	LOD 300 (governs over A2's LOD 200)	Gate audit + report
Deliverable C (100% documentation)	A1 Deliverable C / A2 construction documents	LOD 350, coordination resolved	Gate audit + report
Conformed set	A1 conformance set	LOD 350, addenda incorporated	Conformance audit
Deliverable D (record model)	A1 Deliverable D / A2 consolidated record set	LOD 500 per revised Work Program (LOD 400 as-built in A1)	Record verification, Section 4.4

Deliverable C is proposed at LOD 350 rather than a bare LOD 300 because construction documents that have passed clash resolution carry coordinated interfaces by definition; stating LOD 350 makes that coordination contractual rather than incidental, at no additional modelling cost to disciplines already required to coordinate.

3.6 Model breakdown structure

Consistent with A2, which assigns lighting, acoustics and building enclosure consultants a review and markup role (with the Architect incorporating specialty consultants' work into the architectural Revit model), the federated model comprises:

Model	Author	Notes
Architecture (incl. interiors)	Design consultant / Interior Design	Specialty consultant content incorporated per A2
Structural	Structural engineer	Prototype adapted; delegated design elements as criteria objects
Mechanical (HVAC)	MEPFP engineer	DX/chilled water, hydronic, ductwork systems per A2
Electrical	MEPFP engineer	Power, emergency power, lighting circuits
Plumbing	MEPFP engineer	Including font systems per Owner standards
Fire protection	MEPFP engineer / design-build contractor	Performance design transitions to D-B contractor model in construction
Civil / site	Civil engineer	Grading, utilities, stormwater, access

Contractor / fabrication	General contractor and trades	Onboarded at construction; coordinated, not authored, by the BIM Manager
--------------------------	-------------------------------	--

3.7 Hardware and connectivity requirements

Federating eight or more discipline models for live use in coordination meetings is hardware intensive. The requirements are:

Item	Specification	Provided by
BIM Manager workstation	BimBox class high performance workstation (BimBox SLIM 16" PRO or equivalent specification): 8 core or better CPU, 64 GB RAM, dedicated workstation class GPU with 16 GB or more VRAM, 1 TB or more NVMe storage	BIM Manager; optional one-off priced in Section 6.3
Consultant authoring workstations	Revit 2025 recommended specification or better: multi-core CPU, 32 GB RAM minimum, dedicated GPU, SSD storage	Each consultant
Connectivity	Stable broadband of at least 20 Mbps for model exchange and Owner-platform uploads, readily available in Kampala	Each firm at own office; Symbion at meeting venue

3.8 Fohlio as the asset-data backbone

With no cloud common data environment in the toolset, Fohlio (the Owner's own database) is maximised to carry the structured asset-data role rather than introducing a substitute. In practice this means:

- The model and Fohlio share one identifier per element, so a fixture, fitting or item of equipment in Revit and its Fohlio record are the same object viewed two ways, never two competing entries.
- FF&E, finishes and equipment data originate in or reconcile to Fohlio; the BIM Manager exports the model's asset register in Fohlio's structure and imports Fohlio references back onto model elements at each milestone, so the interiors data pipeline stays current across the programme rather than being rebuilt at handover.
- A monthly Fohlio currency check (model against Fohlio) is reported as a KPI, surfacing drift between the two before it reaches a gate.
- At Deliverable D, the record model is verified against Fohlio so the as-built asset data and the model agree, which is also the foundation of the LOD 500 verification in Section 6.3.
- O&M manuals are published through Fohlio by Interior Design per A1; the BIM Manager ensures the model's asset identifiers match the published O&M records.

3.9 Requirements traceability

Each row maps a documented Owner requirement to the mechanism in this proposal that delivers it, allowing compliance to be checked line by line:

Owner requirement (source)	Delivered by	Reference
Deliverables in PDF and native RVT at every gate (A1 Deliverable A)	Dual format publishing enforced on the exchange calendar; gate audit checks both formats are filed	3.2, 4.2
Revit models developed for project coordination and BIM clash analysis (A1 Phase 2)	Fortnightly Navisworks federation and clash cycle run by the BIM Manager, with chaired Teams sessions	4.2
Meeting materials uploaded to the Owner platform immediately after weekly design meetings (A1 Phase 2)	Standing post-meeting upload task owned by the BIM Manager in the weekly cycle	4.2
Bookmarked, hyperlinked review sessions, two week Owner review, full Owner access (A1)	Sets prepared and uploaded into the Owner platform's review sessions by the BIM Manager	3.1, 4.2
Owner comments resolved before phase completion (A1)	Comment close-out tracking with a monthly KPI until the Owner confirms resolution	4.2, 4.6
LOD 200 at Deliverable A, LOD 300 at Deliverable B per Owner definitions (A1), reconciled with the engineering scope's LOD 200 design development sets (A2)	Unified LOD matrix with the higher A1 requirement governing at Deliverable B; LOD verified at every gate audit	3.5
Updated Revit record model within 60 days of furniture installation (LOD 400 in A1, LOD 500 in the revised Work Program), with native design files, calculation and energy model files and system program files (A1 Deliverable D)	Progressive as-built protocol through construction plus the day by day 60 day close-out plan	4.3, 4.4
Contractor clouds changes and provides as-built documents within 60 days of substantial completion (A1)	Monthly as-built capture audit routing confirmed changes to the owning design consultant	4.3
Co-ted record BIM/drawing set per engineering discipline at end of construction (A2 Phase 5)	Engineers' record sets reconciled against the record model during Deliverable D verification	4.4
Fohlio kept current; O&M manuals published through it (A1)	Fohlio maximised as the asset-data backbone with shared identifiers and a monthly currency KPI	3.8
Specifications on Owner required RIB SpecLink, all disciplines (A2)	SpecLink authoritative; issued specification sets archived with the milestone deliverables	3.1, 3.3
Weekly coordination meetings and unlimited virtual Teams calls (A2)	Teams attendance with live federated model views; cadence table	4.5

4. Execution methodology

4.1 Stage 0: mobilisation (months 1 to 2)

Week 1: obtain the Owner's BIM modeling standards, LOD definitions and the Client's brief through Symbion; fix the shared coordinate system from the site survey; set up the BIM Manager's federation environment and the Owner-platform folder and publishing structure (information states, naming enforcement, transmittal routing). Weeks 2 to 3: localise the Owner's US-authored BIM standards to Ugandan practice (paper sizes, units, code and terminology references) as a discrete task; author and circulate the project BEP for sign-off; lock Revit 2025 project-wide; and hold a kick-off induction with each consultant covering naming, the exchange calendar, the Owner-platform publishing workflow and the clash process. Week 4: first federation of the schematic models received from the Owner's concept package, producing a baseline audit that establishes measurable model health before coordination begins. Weeks 5 to 8: first two full coordination cycles, BEP refinements from live use, and confirmation of the unified milestone schedule against the design programme.

4.2 Stage 1: design coordination (Phase 2, months 1 to 11)

The engine of this stage is a fixed fortnightly rhythm. Consultants publish their models by Tuesday close; the BIM Manager rebuilds the federated model and runs rule-based clash detection in Navisworks on Wednesday (hard clashes plus a discipline tolerance matrix for clearances, access zones and maintenance space); grouped, prioritised clash reports with assigned owners issue Thursday, 48 hours ahead of the coordination session; the session is chaired over Teams against the live federated model, and every issue leaves with an owner and a due date in the clash register, mirrored as a PDF on the Owner platform. Between cycles the weekly design meetings required by A2 are attended with current federated views, and meeting materials are uploaded to the Owner's project management platform immediately after, as A1 requires.

Formal gates punctuate the rhythm: model audits and LOD verification at Deliverable A, Deliverable B (LOD 300) and Deliverable C (LOD 350), each closing with a written compliance report, dual format (PDF + RVT) publication as A1 requires, and a bookmarked, hyperlinked review set uploaded into the Owner's review session for the two week Owner review. A1 permits the session to be administered by the design consultant or the SPD Design Manager; the BIM Manager prepares and administers it on Symbion's behalf, with written responses to every comment tracked to close-out, since A1 makes comment resolution a condition of phase completion. A1's own milestone allowances (4 to 5 months to Deliverable B, a further 4 to 6 months to Deliverable C) mean the calendar is maintained against actual dates, and the fee mechanism in Section 6 absorbs extension without renegotiation.

4.3 Stage 2: construction (Phase 3, 32 months)

The conformed set is aligned with the federated model, and the contractor and key subcontractors are inducted into the BEP, including the design-build fire protection and fire alarm contractors who become engineers of record under A2 and whose models join the federation at that point. The as-built protocol then runs monthly: the contractor clouds and references changes in official project documentation per A1; the BIM Manager audits that capture every month and routes confirmed changes to the owning design consultant for model update, so that the record model accretes progressively across 32 months rather than reconstructed at handover. Because the engineering consultants' construction stage

engagement is capped under A2 (limited site observations, two submittal review cycles, ten day RFI turnaround), the monthly audit is also the early warning system that flags when as-built information is outrunning the consultants' remaining capacity, in time for Symbion to act. Reporting moves to the monthly cadence in Section 4.5 with quarterly model health audits.

4.4 Stage 3: close-out and Deliverable D (within 60 days of furniture installation)

Day 1 to 10: reconcile the contractor's final as-built documentation (due to the design consultant within 60 days of substantial completion per A1) against the progressively maintained model and the engineers' consolidated record sets. Day 10 to 35: verify the LOD 500 record model discipline by discipline, including element-level asset data, parameter completeness and naming compliance with the Owner's standards. Day 35 to 50: assemble the native design model files, calculation and energy model files and system program files A1 requires alongside the record model. Day 50 to 60: support Symbion's submission to the Owner's catalog and project management platform, and archive the complete project information set.

4.5 Meetings and reporting cadence

Activity	Design stage	Construction stage
Design coordination meeting (Teams)	Weekly, per A2	As scheduled by Symbion
Model coordination session (chaired)	Fortnightly	Monthly
Federation and clash cycle	Fortnightly	Monthly
BIM status report	Monthly	Monthly
Model health audit	Per deliverable gate	Quarterly
Site presence	As required (Kampala based)	Up to two visits per month

4.6 Key performance indicators

The monthly report tracks a fixed KPI set so that model quality is a measured fact rather than an opinion: open clash count and fortnight on fortnight burn-down by discipline; model health score per model (warnings, duplicate elements, unplaced rooms, file size trend); naming and metadata compliance percentage; exchange punctuality (models published on time against the calendar); review comment close-out rate per Owner session; and, in construction, as-built capture currency (the lag in days between confirmed site change and model update). Persistent adverse KPIs are escalated to Symbion with a named owner and a recommended action.

5. Programme and resourcing

Resourcing follows the Owner's revised Work Program. Loading is not uniform: it is highest while documents are being produced, low during tender, and at a steady part-time level through construction.

Work Program stage	LOD	Duration	Indicative loading
--------------------	-----	----------	--------------------

2.1 Basis of Design	LOD 200	1 month	Mobilisation plus near full time
2.2 50% / Deliverable B	LOD 300	3 months	Full coordination
2.3 100% / Deliverable C	LOD 350	4 months	Full coordination
2.4 Tender, negotiation, award	—	3 months	Reduced watching brief; clash cycles paused, query support and model currency only
2.5 Conformed Set	LOD 350	within above	Addenda incorporation at award
3.1 Building supervision	LOD 400	32 months	Approximately 20 to 25% of full time
3.2 FFE installation supervision	LOD 400	4 months	Lighter supervision loading
3.3 Close-out / Deliverable D (LOD 500)	LOD 500	2 months	Distinct deliverable: field-verified asset data

A single named BIM Manager carries the role throughout, providing the continuity of project knowledge that multi-year coordination depends on. Mobilisation can commence within five working days of appointment.

6. Financial proposal

All amounts are in United States dollars and exclude VAT. The fee is priced directly against the Owner's revised Work Program, with documentation loading reflected month by month rather than as a single flat rate. Software and hardware are listed separately in Sections 6.2 and 6.3 as optional, itemised provisions, because neither forms part of the Owner-provided environment used by the other consultants.

6.1 Services fee

Work Program stage	Basis	Rate (USD)	Qty	Amount (USD)
Documentation (2.1 to 2.3: BOD, 50%, 100%) including mobilisation, standards localisation and gate audits	Per month	2,450	8	19,600
Tender, negotiation and award (2.4) at reduced watching-brief rate	Per month	950	3	2,850
Building construction supervision (3.1)	Per month	1,300	32	41,600
FFE installation supervision (3.2), lighter loading	Per month	800	4	3,200
Close-out / Deliverable D at LOD 500 (3.3), separate 2 month deliverable	Fixed	4,500	1	4,500

Total services fee (excluding VAT)				71,750
---	--	--	--	---------------

The monthly rates are trimmed across all stages in response to Symbion's request to reduce the offer, and the three month tender period is charged at a reduced watching-brief rate of USD 950 since active coordination pauses during tender. The revised Work Program separates Phase 3 into three deliverables totalling 38 months (building supervision 32, furniture supervision 4, close-out 2), and the LOD 500 Deliverable D is a distinct line rather than a folded-in task; both are priced here as the program presents them. The net effect is a reduction from the rates set against an increase from the scope the program itself separated out.

6.2 Software (optional, at cost)

The other consultants licence their own authoring software; the BIM Manager needs one Autodesk seat to review, federate and verify models. If the Owner or Symbion does not provide it, it is offered here at cost:

Item	Basis	Amount (USD)
Autodesk AEC Collection (Revit 2025 + Navisworks Manage), single named-user seat, current list approx. USD 3,375 per year	Per year, at cost	3,375 / yr
Indicative total over the 49 month programme (approx. 4.1 years), at cost against the vendor invoice		13,840

Invoiced at cost against the vendor invoice; the at-cost basis governs over the indicative figure. No cloud subscription (BIM Collaborate Pro or equivalent) is included, consistent with using only the Owner-provided environment.

6.3 Hardware (optional, one-off)

Federating six buildings across eight or more disciplines for live use in coordination meetings requires a workstation specified for the task. If not otherwise provided, the BIM Manager supplies one:

Item	Specification	Amount (USD)
BimBox SLIM 16-inch PRO mobile workstation (or equivalent)	Intel Core Ultra 9 275HX, RTX 5090 24 GB, 64 GB DDR5, 1 TB or more NVMe	approx. 5,325

Stated as a one-off capital item at current manufacturer pricing. An equivalent-specification workstation from another vendor may be substituted at comparable or lower cost. This item is included only if Symbion wishes the BIM Manager to carry the hardware; otherwise it is omitted.

6.4 Deliverable D at LOD 500

The revised Work Program lists the LOD 500 Deliverable D (item 3.3) as a distinct two month Phase 3 deliverable, separate from the LOD 400 building and furniture supervision (items 3.1 and 3.2). It is priced accordingly as a separate fixed line of USD 4,500 in Section 6.1, rather than folded into the supervision fee. LOD 500 is a field-verified, fully attributed representation: each element is confirmed against the constructed building and carries complete asset data, reconciled against Fohlio per Section 3.8. For the record, the original invitation and Attachment A1 specified LOD 400 as the record-model definition; the revised Work Program adds LOD 500 as the close-out deliverable, and the distinction is noted here so the change is on the record. Because LOD 500 depends on the completeness of the contractor's commissioning and asset data, its detailed acceptance criteria are best fixed once the construction information requirements are set.

6.5 Rates for extension and additional services

- Programme extension: each documentation month beyond the eight programmed is charged at USD 2,450, each tender month beyond three at USD 950, each building supervision month beyond 32 at USD 1,300, and each furniture supervision month beyond four at USD 800, adjusted by the escalation provision below where the extension month falls after month 24. The monthly rate continues without a claims process.
- Additional services (items in Section 2.2, extra clash cycles beyond two additional per gate, or separately agreed modelling support): USD 28 per hour, quoted in advance for any task expected to exceed 20 hours.

6.6 Payment terms

- Invoicing monthly in arrears; software, if carried by the BIM Manager under Section 6.2, invoiced annually at cost against the vendor invoice; the close-out fee invoiced on submission of the verified record model.
- Payment within 30 days of invoice. If an invoice remains unpaid 30 days after the due date, services may be suspended on 14 days written notice until the account is settled; suspension does not relieve the payment obligation, the programme extends by the suspension period, and services resume within five working days of settlement at no remobilisation charge.
- Rates are fixed for the first 24 months from appointment and escalate by 5% per annum thereafter, reflecting the multi-year programme.
- Fees are quoted exclusive of VAT (currently 18% in Uganda) and net of withholding tax: where Symbion is required by law to withhold tax at source, invoiced amounts are grossed up so the net amount received equals the fees stated, and withholding tax credit certificates are provided for all amounts withheld.

7. Commercial terms and basis

The fee in Section 6 rests on the following terms. They are stated as the working basis of the engagement; where project information issued after appointment materially differs, the affected term is adjusted by agreement before additional cost is incurred.

1. Authoring boundary. The role is management, coordination and verification only. No discipline model, including the record model, is authored by the BIM Manager; the record

model is produced by the design consultants from contractor as-built documentation per A1 Deliverable D and verified under this engagement.

2. LOD framework. LOD applies per the Owner's definitions. Deliverable D is priced at LOD 500 per the revised Work Program (Section 6.4); the original brief and Attachment A1 specified LOD 400, and the change is noted for the record. The Owner's BIM modeling standards are adopted in full upon issue, localised to Ugandan practice at mobilisation, and take precedence over interim ISO 19650 conventions.

3. Software and hardware. This engagement uses only the Owner-provided environment plus the BIM Manager's own Autodesk seat (Section 6.2) and workstation (Section 6.3), both optional and itemised. No cloud common data environment is introduced. Every other firm provides its own authoring software and hardware.

4. Programme basis. The programme follows the Owner's revised Work Program: 11 months documentation (eight active plus three tender) and 32 months construction. Extension is handled automatically at the monthly rates in Section 6.4; programme risk is carried through this mechanism rather than through contingency in the base fee.

5. Model count. Coordination covers the model breakdown in Section 3.6, up to ten concurrent models including contractor and design-build models during construction. A materially larger model set is a change.

6. Close-out and defects liability. The revised Work Program provides a separate 2 month LOD 500 close-out for Deliverable D (item 3.3), covered by the fixed fee in Section 6.1. Any recurring services requested during a defects liability period are charged at the hourly rate in Section 6.4.

7. Input dependency. Consultants publish native Revit 2025 models on shared coordinates per the exchange calendar. Re-coordination caused by late design changes after Deliverable C sign-off, beyond two additional clash cycles, is an additional service.

8. Site presence. Up to two site visits per month during construction are included; the consultant is Kampala based so visits carry no travel premium. Standing full time site presence would require a revised Phase 3 rate.

9. Insurance. No professional indemnity insurance is included in the fee. Should the Owner or Symbion require specified PI cover, it will be arranged and charged at documented premium cost.

10. Intellectual property. Models and project information are the Owner's property per A1, including submission to the Owner's catalog at Deliverable D. The consultant retains ownership of pre-existing tools, templates and know-how and grants a licence for their project output.

11. Currency. Fees are in USD; payment in Uganda shillings converts at the Bank of Uganda mid-rate on the invoice date.

12. Contract form. Engagement is as sub-consultant to Symbion under a simple consultancy agreement. Payment to the BIM Manager is not conditional on Symbion's receipt of payment from the Owner. Either party may terminate on 60 days written notice, with fees payable to the termination date plus committed software costs.

8. Acceptance

This proposal is open for acceptance for 30 days from 17 June 2026, by signed copy of this document or by issue of a sub-consultancy agreement consistent with Sections 6 and 7, whichever is earlier. Mobilisation commences within five working days of appointment.

For the Consultant:

Name: Mayanja Davis, BIM/CAD Specialist

Signature:



Date: 17/06/2026

For Symbion Consulting Group Studios:

Name: _____

Signature: _____ Date: _____