

BIM management and coordination services

Technical proposal, execution methodology and financial offer

Project: **Kampala Uganda Temple Project**

Prepared for: **Symbion Consulting Group Studios**

Attention: **Ronald Katabira MCIOB, Director**

Prepared by: **Mayanja Davis, BIM/CAD Specialist**

Contact: **mayanjadavis@gmail.com | +256 787 472 999**

Date: **11 June 2026**

Reference: **DV-BIM-PRO-001, v2**

Contents

Executive summary.....	3
1. Project understanding	3
1.1 The development.....	3
1.2 The delivery framework	4
1.3 The BIM Manager role	4
2. Scope of services.....	4
2.1 Services included	4
2.2 Services excluded	5
3. Proposed BIM environment.....	6
3.1 The Owner-mandated environment, adopted as found	6
3.2 Completing the environment where the documents are silent	7
3.3 Information hierarchy: one source of truth per information type	8
3.4 Standards and naming.....	8
3.5 Unified LOD matrix	8
3.6 Model breakdown structure	9
3.7 Hardware and connectivity requirements	9
3.8 Requirements traceability	10
4. Execution methodology	11
4.1 Stage 0: mobilisation (months 1 to 2).....	11
4.2 Stage 1: design coordination (Phase 2 documentation, months 1 to 8).....	11
4.3 Stage 2: construction (Phase 3, 32 months)	12
4.4 Stage 3: close-out and Deliverable D (within 60 days of furniture installation)	12
4.5 Meetings and reporting cadence.....	12
4.6 Key performance indicators	12
5. Programme and resourcing.....	13
6. Financial proposal.....	13
6.1 Rates for extension and additional services.....	14
6.2 Payment terms	14
7. Commercial terms and basis.....	14
8. Acceptance	15

Executive summary

Symbion Consulting Group Studios requires BIM Manager coordination services for the Kampala Uganda Temple Project: six buildings totalling approximately 6,597 m² on a six acre site in Kampala's central business district, delivered over a 52 month programme (8 months documentation, 32 months construction supervision, 12 months defects liability), ending in as-built information at LOD 400 as the Owner defines it.

The challenge in this engagement is not modelling; it is keeping eight or more design disciplines, two scope frameworks (the Owner's A1 phases and the engineering A2 phases), and later a contractor, exchanging accurate models against one calendar on one platform, so that the Owner receives a verified LOD 400 record model within 60 days of furniture installation.

This proposal is built directly from the Owner's documented requirements. The Owner already operates a defined delivery ecosystem: Revit as the authoring platform, an Owner project management platform for all PDF deliverables and approvals, bookmarked and hyperlinked review sessions with two week Owner review periods, Fohlio for furniture, fixtures, equipment and O&M data, RIB SpecLink for specifications, Microsoft Teams for coordination calls and the Niagara framework for building controls. Section 3 adopts every one of those mandates as found, and adds tools only in the four places the documents are deliberately silent (the Revit version, the model environment, the clash toolset and the review product), choosing the options that integrate most directly with what the Owner already runs: Revit 2025, Autodesk Construction Cloud, Navisworks Manage and Bluebeam Studio. A requirements traceability table in Section 3.8 maps each Owner requirement to the mechanism in this proposal that delivers it.

The total fee is USD 92,400 excluding VAT, fully inclusive of the BIM Manager's software (Autodesk AEC Collection, ACC BIM Collaborate Pro and Bluebeam Revu seats for the full 52 months) and hardware (a BIMBox class high performance workstation), structured as USD 2,600 per month during documentation, USD 1,450 per month during construction, a fixed USD 3,500 close-out fee and USD 21,700 of at-cost software provision. There are no provisional sums, no items awaiting confirmation, and no unstated software or hardware dependencies: the offer can be accepted as written and mobilised within five working days.

1. Project understanding

1.1 The development

Building	Approximate gross area
Temple	2,449 m ²
Meetinghouse	1,312 m ²
Housing / ancillary building	2,554 m ²
Grounds building	93 m ²
Utility building	166 m ²
Guard house	23 m ²
Total	Approximately 6,597 m²

Concept and schematic design are complete. The temple is developed from an Owner prototype (the engineering scope references the 1-40 F prototype) with significant site adaptation, and the design team spans architecture, interior design, structural, mechanical, electrical, plumbing, fire protection, civil, architectural lighting, acoustics and building enclosure disciplines, supported by quantity surveying and Owner peer reviewers.

1.2 The delivery framework

Two scope documents govern the work. Attachment A1 (the Owner's architectural and engineering design scope) structures the project as Phase 1 leadership approvals, Phase 2 documentation with Deliverables A (Basis of Design, LOD 200), B (50% documentation, LOD 300) and C (100% documentation) plus a conformed set, and Phase 3 construction administration ending in Deliverable D, an updated Revit record model at LOD 400 reflecting as-built conditions, due within 60 days of furniture installation. Attachment A2 (the engineering scope) structures the same work as Phase 2 design development, Phase 3 zoning, Phase 4 construction documents and Phase 5 construction administration, with each engineering discipline issuing 50% coordination and 100% sets per phase and a consolidated record BIM/drawing set at the end of construction.

These two frameworks describe one project with two numbering systems and, in one instance, two LOD values for the same milestone (A1 sets Deliverable B at LOD 300 while A2 sets design development deliverables at BIM LOD 200). Reconciling them into a single BIM milestone schedule and a single LOD matrix is the first task of this engagement, and Section 3.5 of this proposal does so.

1.3 The BIM Manager role

The role proposed is information management, coordination and verification: establishing the BIM environment, running the federation and clash process, auditing model quality at every contractual gate, managing the construction stage flow of as-built information, and verifying the Deliverable D record model before submission to the Owner. Model authoring remains with the design consultants and the contractor; the boundary is defined precisely in Section 2.

2. Scope of services

2.1 Services included

- BIM Execution Plan (BEP): authored within the first month, implementing the Owner's BIM modeling standards and LOD definitions, and covering roles and responsibilities, the model breakdown structure in Section 3.6, the unified LOD matrix in Section 3.5, naming conventions, shared coordinates and the master and task information delivery plans (MIDP/TIDP), aligned with ISO 19650 principles.
- Common data environment: build and day to day administration of the Autodesk Construction Cloud project described in Section 3.2, including folder structure, ISO 19650 information states, access rights, publishing workflows and onboarding of every consultant and, later, the contractor.
- Federation and clash detection: a fortnightly cycle in Navisworks Manage and ACC Model Coordination across all discipline models, with prioritised, grouped clash reports issued 48 hours before each coordination session, issues tracked to closure in ACC, and the coordination sessions chaired by the BIM Manager.

- Model quality audits and LOD verification at each contractual gate: Deliverable A, Deliverable B, Deliverable C, the conformed set, and quarterly during construction, each closed with a written compliance report Symbion can place in front of the Owner alongside the drawing deliverables.
- Unified BIM milestone schedule reconciling the A1 and A2 phase frameworks so all disciplines exchange against one calendar, maintained weekly against actual milestone dates.
- Design meeting support: attendance at the weekly design coordination meetings the engineering scope requires, with federated model views prepared for live use in those meetings, and upload of coordination materials to the Owner's project management platform immediately after each meeting as A1 requires.
- Construction stage model management: onboarding the contractor and key subcontractors to the BEP, administering the model side of submittals and requests for information (RFIs) where model relevant, and operating the progressive as-built capture protocol in Section 4.3 so as-built information accumulates monthly rather than arriving at handover.
- Record model verification: within the 60 day Deliverable D window, verification of the LOD 400 record model against the contractor's as-built documentation and the engineers' consolidated record sets, with parameter and naming compliance confirmed before submission to the Owner's catalog.
- Reporting: the monthly BIM status report and key performance indicators defined in Section 4.6.
- Training and onboarding: a CDE and BEP induction for each consultant team at mobilisation, and a contractor induction at construction commencement.

2.2 Services excluded

The following are outside the fee in Section 6 and available as additional services at the rates stated there:

- Model authoring of any discipline, including production or upgrading of the LOD 400 record model. Authoring remains with the design consultants (who author the record model from contractor as-built documentation per A1) and the contractor; this role coordinates and verifies.
- Quantity take-off, 4D programme simulation, 5D cost modelling, energy simulation, renderings and visualisations beyond coordination views.
- Scan to BIM, point cloud surveys and laser scanning verification of as-built conditions.
- COBie or other structured asset data deliverables. A1's Deliverable D requires the LOD 400 record model, native design files and O&M documentation (the latter published through Fohlio by Interior Design); structured COBie is not required by the documents and is therefore excluded, and can be quoted separately should the Owner request it.
- Site supervision, design responsibility and code compliance checking, which remain with the design consultants and the supervising team.
- Software licences and seats for other consultants and the contractor, each of whom provides their own authoring and ACC seats per standard industry practice. The BIM Manager's own seats are included in this fee (Section 6).

3. Proposed BIM environment

The starting point of this engagement is that the Owner has already designed most of the delivery environment, and the BIM Manager's first duty is to implement it faithfully. Section 3.1 lists the Owner's mandates exactly as the documents state them. Section 3.2 completes the environment in the four places the documents are silent. Everything that follows, including the LOD matrix and the requirements traceability table, exists to make Owner compliance demonstrable rather than asserted.

3.1 The Owner-mandated environment, adopted as found

Owner mandate (source)	What the documents require	How this engagement complies
Autodesk Revit (A1 Deliverables A to D)	Every deliverable in both PDF and native RVT; Revit models developed for project coordination and BIM clash analysis; the final record model is an updated Revit model at LOD 400.	Revit is the sole authoring platform; every gate deliverable is published dual format (PDF + RVT); the record model is verified in Revit.
Owner project management platform (A1)	All PDF documents uploaded to the Owner's platform; materials from weekly design meetings uploaded immediately after each meeting as a single dated PDF or PPT.	The post-meeting upload is a standing BIM Manager task in the weekly cycle (Section 4.2); the Owner platform remains the authoritative home of deliverables and approvals.
Review sessions (A1 Deliverable A, peer review)	PDF deliverable sets uploaded into bookmarked, hyperlinked review sessions, administered by the design consultant or the SPD Design Manager, with full Owner access, a two week minimum review, and written responses to every comment; comments must be resolved before a phase is complete.	Sessions built and administered on Symbion's behalf in Bluebeam Studio at every gate, with comment close-out tracked as a KPI until the Owner confirms resolution (Sections 4.2, 4.6).
Owner BIM modeling standards and LOD definitions (A1)	LOD is defined by the Owner's own standards, in which LOD 400 constitutes as-built information.	Adopted in full upon issue and supreme over interim conventions; implemented through the unified LOD matrix (Section 3.5).
Fohlio (A1)	The Owner's specification database for all furniture, fixtures, equipment and finishes; budgets and progress reports generated from it; O&M manuals published through it at close-out.	Fohlio remains authoritative for its domain; the CDE links to it and never duplicates it (Section 3.3).
RIB SpecLink (A2, all disciplines)	Full specifications written on the Owner required SpecLink platform.	SpecLink remains authoritative for specifications; issued sets are archived in the CDE per milestone.
Microsoft Teams (A2)	Weekly coordination meetings and unlimited virtual coordination Teams calls.	All meetings run on Teams with live federated model views shared in-call.

Niagara (A2 peer review)	Every building management system controller uses the Niagara platform.	Noted as a coordination requirement for the BMS model content and controls submittals.
Fee discipline (A1 Phase 2)	Work completed without advance Owner approval may not be compensated.	Mirrored in this engagement's own change discipline: nothing beyond the stated scope proceeds without written instruction (Section 7).

3.2 Completing the environment where the documents are silent

The documents name no Revit version, no model environment, no clash toolset and no review product. The four selections below fill those silences with the options that integrate most directly with the Owner's named platforms:

Layer	Product	Role	Provided by
Authoring	Autodesk Revit 2025	All discipline models. Version locked project-wide at kick-off; Revit 2025 is the mature, fully ACC-integrated release, and a locked version prevents the upgrade incompatibilities that fragment multi-year projects.	Each consultant (AEC Collection)
CDE	Autodesk Construction Cloud (Autodesk Docs)	Single home for all models and coordination information, structured into ISO 19650 work in progress, shared, published and archive states with approval workflows.	Project ACC hub; each firm its own seats
Cloud worksharing and coordination	ACC BIM Collaborate Pro	Live multi-firm Revit collaboration, automated model coordination spaces, and closed-loop issue tracking inside Revit and Navisworks.	Each consultant; BIM Manager seat in this fee
Federation and clash	Navisworks Manage 2025	Fortnightly federated model, rule-based clash detection with discipline tolerance matrix, NWD milestone archives forming the audit trail.	BIM Manager (in this fee)
Design review	Bluebeam Revu / Studio Sessions	The bookmarked, hyperlinked deliverable review sessions A1 requires, administered by the BIM Manager or the Owner's Design Manager with full Owner team access.	BIM Manager seat in this fee; reviewers free via Studio
Meetings	Microsoft Teams	Weekly design coordination and unlimited virtual coordination calls, as named in the engineering scope.	Symbion (existing)

Owner systems	Owner PM platform, Fohlio, RIB SpecLink, Niagara	Authoritative for PDF deliverables and approvals, FF&E and O&M data, specifications, and building controls respectively. The CDE links to them; it does not replace them.	Owner
---------------	--	---	-------

3.3 Information hierarchy: one source of truth per information type

Coordination breaks down when two platforms hold competing versions of the same information, so the hierarchy is explicit:

Information type	Authoritative platform	Secondary record
Models (RVT, NWD, IFC)	ACC (Autodesk Docs)	Milestone NWDs archived per gate
PDF deliverables and Owner approvals	Owner project management platform	Issue record mirrored in ACC
Review comments on deliverables	Bluebeam Studio session	Comment close-out log in ACC
Coordination issues and clashes	ACC Issues	Fortnightly clash report PDF
FF&E, finishes, O&M	Fohlio	Linked, not duplicated
Specifications	RIB SpecLink	Issued sets archived in ACC

3.4 Standards and naming

Information management follows ISO 19650-2 adapted to the Owner's BIM modeling standards, which are adopted in full upon issue and take precedence wherever they differ. Until issued, the BEP applies an ISO 19650 container naming convention of the form KUT-ZZZ-XX-XX-M3-A-0001 (project, originator, volume, level, type, discipline, number), a shared site coordinate system fixed at mobilisation from the survey, and millimetre units across all disciplines. Every model exchange carries a model suitability code, so no consultant ever builds against superseded information.

3.5 Unified LOD matrix

The matrix below reconciles the two scope documents into one ruler, applying the Owner's LOD definitions (in which LOD 400 constitutes as-built information). Where A1 and A2 differ at the 50% documentation milestone, the higher A1 requirement (LOD 300) governs, because Deliverable B is the Owner's contractual review gate:

Milestone	A1 / A2 reference	Model LOD	Verification gate
Deliverable A (Basis of Design)	A1 Phase 2 / A2 carried from SD	LOD 200	Baseline audit
Deliverable B (50% documentation)	A1 Deliverable B / A2 design development	LOD 300 (governs over A2's LOD 200)	Gate audit + report

Deliverable C (100% documentation)	A1 Deliverable C / A2 construction documents	LOD 350, coordination resolved	Gate audit + report
Conformed set	A1 conformance set	LOD 350, addenda incorporated	Conformance audit
Deliverable D (record model)	A1 Deliverable D / A2 consolidated record set	LOD 400, as-built per Owner definition	Record verification, Section 4.4

Deliverable C is proposed at LOD 350 rather than a bare LOD 300 because construction documents that have passed clash resolution carry coordinated interfaces by definition; stating LOD 350 makes that coordination contractual rather than incidental, at no additional modelling cost to disciplines already required to coordinate.

3.6 Model breakdown structure

Consistent with A2, which assigns lighting, acoustics and building enclosure consultants a review and markup role (with the Architect incorporating specialty consultants' work into the architectural Revit model), the federated model comprises:

Model	Author	Notes
Architecture (incl. interiors)	Design consultant / Interior Design	Specialty consultant content incorporated per A2
Structural	Structural engineer	Prototype adapted; delegated design elements as criteria objects
Mechanical (HVAC)	MEPFP engineer	DX/chilled water, hydronic, ductwork systems per A2
Electrical	MEPFP engineer	Power, emergency power, lighting circuits
Plumbing	MEPFP engineer	Including font systems per Owner standards
Fire protection	MEPFP engineer / design-build contractor	Performance design transitions to D-B contractor model in construction
Civil / site	Civil engineer	Grading, utilities, stormwater, access
Contractor / fabrication	General contractor and trades	Onboarded at construction; coordinated, not authored, by the BIM Manager

3.7 Hardware and connectivity requirements

Federating eight or more discipline models for live use in coordination meetings is hardware intensive. The requirements are:

Item	Specification	Provided by
------	---------------	-------------

BIM Manager workstation	BIMBox class high performance workstation (BIMBox SLIM 16" PRO or equivalent specification): 8 core or better CPU, 64 GB RAM, dedicated workstation class GPU with 12 GB or more VRAM, 1 TB NVMe storage	BIM Manager, included in this fee at no cost to the project
Consultant authoring workstations	Revit 2025 recommended specification or better: multi-core CPU, 32 GB RAM minimum, dedicated GPU, SSD storage	Each consultant
Connectivity	Stable broadband of at least 20 Mbps per authoring seat for ACC cloud worksharing sync, readily available in Kampala	Each firm at own office; Symbion at meeting venue

3.8 Requirements traceability

Each row maps a documented Owner requirement to the mechanism in this proposal that delivers it, allowing compliance to be checked line by line:

Owner requirement (source)	Delivered by	Reference
Deliverables in PDF and native RVT at every gate (A1 Deliverable A)	Dual format publishing enforced on the exchange calendar; gate audit checks both formats are filed	3.2, 4.2
Revit models developed for project coordination and BIM clash analysis (A1 Phase 2)	Fortnightly Navisworks and ACC Model Coordination federation and clash cycle with chaired sessions	4.2
Meeting materials uploaded to the Owner platform immediately after weekly design meetings (A1 Phase 2)	Standing post-meeting upload task owned by the BIM Manager in the weekly cycle	4.2
Bookmarked, hyperlinked review sessions, two week Owner review, full Owner access (A1)	Bluebeam Studio sessions built and administered on Symbion's behalf at every gate	3.1, 4.2
Owner comments resolved before phase completion (A1)	Comment close-out tracking with a monthly KPI until the Owner confirms resolution	4.2, 4.6
LOD 200 at Deliverable A, LOD 300 at Deliverable B per Owner definitions (A1), reconciled with the engineering scope's LOD 200 design development sets (A2)	Unified LOD matrix with the higher A1 requirement governing at Deliverable B; LOD verified at every gate audit	3.5
Updated Revit record model at LOD 400 within 60 days of furniture installation, with native design files, calculation and energy model files and system program files (A1 Deliverable D)	Progressive as-built protocol through construction plus the day by day 60 day close-out plan	4.3, 4.4

Contractor clouds changes and provides as-built documents within 60 days of substantial completion (A1)	Monthly as-built capture audit routing confirmed changes to the owning design consultant	4.3
Consolidated record BIM/drawing set per engineering discipline at end of construction (A2 Phase 5)	Engineers' record sets reconciled against the record model during Deliverable D verification	4.4
Fohlio kept current; O&M manuals published through it (A1)	Fohlio authoritative for FF&E and O&M; CDE links, never duplicates	3.1, 3.3
Specifications on Owner required RIB SpecLink, all disciplines (A2)	SpecLink authoritative; issued specification sets archived in the CDE per milestone	3.1, 3.3
Weekly coordination meetings and unlimited virtual Teams calls (A2)	Teams attendance with live federated model views; cadence table	4.5

4. Execution methodology

4.1 Stage 0: mobilisation (months 1 to 2)

Week 1: obtain the Owner's BIM modeling standards, LOD definitions and the Client's brief through Symbion; fix the shared coordinate system from the site survey; build the ACC project (folder structure, information states, naming enforcement, permission groups). Weeks 2 to 3: author and circulate the project BEP for sign-off, lock Revit 2025 project-wide, and hold a kick-off induction with each consultant covering the CDE, naming, exchange calendar and clash process. Week 4: first federation of the schematic models received from the Owner's concept package, producing a baseline audit that establishes measurable model health before coordination begins. Weeks 5 to 8: first two full coordination cycles, BEP refinements from live use, and confirmation of the unified milestone schedule against the design programme.

4.2 Stage 1: design coordination (Phase 2 documentation, months 1 to 8)

The engine of this stage is a fixed fortnightly rhythm. Consultants publish to the shared state by Tuesday close; the federated model is rebuilt and rule-based clash detection runs Wednesday (hard clashes plus a discipline tolerance matrix for clearances, access zones and maintenance space); grouped, prioritised clash reports with assigned owners issue Thursday, 48 hours ahead of the coordination session; the session is chaired against the live federated model, and every issue leaves with an owner and a due date tracked in ACC Issues. Between cycles the weekly design meetings required by A2 are attended with current federated views, and meeting materials are uploaded to the Owner's project management platform immediately after, as A1 requires.

Formal gates punctuate the rhythm: model audits and LOD verification at Deliverable A, Deliverable B (LOD 300) and Deliverable C (LOD 350), each closing with a written compliance report, dual format (PDF + RVT) publication as A1 requires, and a Bluebeam Studio review session built bookmarked and hyperlinked for the Owner's two week review. A1 permits the session to be administered by the design consultant or the SPD Design Manager; under this engagement it is administered on Symbion's behalf, with written responses to every comment tracked to close-out, since A1 makes comment resolution a condition of phase completion. A1's own milestone allowances (4 to 5 months to Deliverable B, a further 4 to 6 months to

Deliverable C) mean the calendar is maintained against actual dates, and the fee mechanism in Section 6 absorbs extension without renegotiation.

4.3 Stage 2: construction (Phase 3, 32 months)

The conformed set is aligned with the federated model, and the contractor and key subcontractors are inducted into the BEP, including the design-build fire protection and fire alarm contractors who become engineers of record under A2 and whose models join the federation at that point. The as-built protocol then runs monthly: the contractor clouds and references changes in official project documentation per A1; the BIM Manager audits that capture every month and routes confirmed changes to the owning design consultant for model update, so that the record model accretes progressively across 32 months rather than reconstructed at handover. Because the engineering consultants' construction stage engagement is capped under A2 (limited site observations, two submittal review cycles, ten day RFI turnaround), the monthly audit is also the early warning system that flags when as-built information is outrunning the consultants' remaining capacity, in time for Symbion to act. Reporting moves to the monthly cadence in Section 4.5 with quarterly model health audits.

4.4 Stage 3: close-out and Deliverable D (within 60 days of furniture installation)

Day 1 to 10: reconcile the contractor's final as-built documentation (due to the design consultant within 60 days of substantial completion per A1) against the progressively maintained model and the engineers' consolidated record sets. Day 10 to 35: verify the LOD 400 record model discipline by discipline, including parameter completeness and naming compliance with the Owner's standards. Day 35 to 50: assemble the native design model files, calculation and energy model files and system program files A1 requires alongside the record model. Day 50 to 60: support Symbion's submission to the Owner's catalog and project management platform, and archive the complete CDE.

4.5 Meetings and reporting cadence

Activity	Design stage	Construction stage
Design coordination meeting (Teams)	Weekly, per A2	As scheduled by Symbion
Model coordination session (chaired)	Fortnightly	Monthly
Federation and clash cycle	Fortnightly	Monthly
BIM status report	Monthly	Monthly
Model health audit	Per deliverable gate	Quarterly
Site presence	As required (Kampala based)	Up to two visits per month

4.6 Key performance indicators

The monthly report tracks a fixed KPI set so that model quality is a measured fact rather than an opinion: open clash count and fortnight on fortnight burn-down by discipline; model health score per model (warnings, duplicate elements, unplaced rooms, file size trend); naming and metadata compliance percentage; exchange punctuality (models published on time against the calendar); review comment close-out rate per Owner session; and, in construction, as-built

capture currency (the lag in days between confirmed site change and model update). Persistent adverse KPIs are escalated to Symbion with a named owner and a recommended action.

5. Programme and resourcing

The fee is built bottom-up from approximately 2,400 hours over the engagement:

Stage	Period	Indicative loading
Mobilisation and BEP	Months 1 to 2	Near full time
Design coordination	Months 3 to 8 (Phase 2)	Approximately 50% of full time
Construction	32 months (Phase 3)	Approximately 20 to 25% of full time
Close-out	60 day Deliverable D window	Fixed task

A single named BIM Manager carries the role throughout the 52 month programme, providing the continuity of project knowledge that multi-year coordination depends on. Mobilisation can commence within five working days of appointment, ahead of the project commencement next month.

6. Financial proposal

All amounts are in United States dollars and exclude VAT. The fee is complete: it includes the BIM Manager's software seats and workstation for the full programme, so no provisional sums or third party cost items remain.

Item	Basis	Rate (USD)	Qty	Amount (USD)
Phase 2 BIM management (BEP, CDE, coordination, gate audits)	Per month	2,600	8	20,800
Phase 3 construction stage BIM management	Per month	1,450	32	46,400
Close-out: Deliverable D record model verification and handover support	Fixed	3,500	1	3,500
Software provision: BIM Manager seats of Autodesk AEC Collection (Revit 2025 + Navisworks Manage, list USD 3,375/yr), ACC BIM Collaborate Pro (list USD 945/yr) and Bluebeam Revu (list USD 330/yr), at cost with increase allowance	Per year, pro rata	5,000	52 mo	21,700
Total fee (excluding VAT)				92,400

Should Symbion or the Owner elect to provide the software seats through a project ACC hub or existing subscriptions, the software line is removed and the total fee reduces to USD 70,700, at Symbion's election.

6.1 Rates for extension and additional services

- Programme extension: each month of Phase 2 beyond 8 months is charged at USD 2,600 and each month of Phase 3 beyond 32 months at USD 1,450, in each case adjusted by the escalation provision below where the extension month falls after month 24, with software continuing pro rata. The monthly rate continues without a claims process.
- Additional services (items in Section 2.2, extra clash cycles beyond two additional per gate, or separately agreed modelling support): USD 28 per hour, quoted in advance for any task expected to exceed 20 hours.

6.2 Payment terms

- Invoicing monthly in arrears; software invoiced annually at cost against vendor invoices; the close-out fee invoiced on submission of the verified record model.
- Payment within 30 days of invoice. If an invoice remains unpaid 30 days after the due date, services may be suspended on 14 days written notice until the account is settled; suspension does not relieve the payment obligation, the programme extends by the suspension period, and services resume within five working days of settlement at no remobilisation charge.
- Rates are fixed for the first 24 months from appointment and escalate by 5% per annum thereafter, reflecting the 52 month programme.
- Fees are quoted exclusive of VAT (currently 18% in Uganda) and net of withholding tax: where Symbion is required by law to withhold tax at source, invoiced amounts are grossed up so the net amount received equals the fees stated, and withholding tax credit certificates are provided for all amounts withheld.

7. Commercial terms and basis

The fee in Section 6 rests on the following terms. They are stated as the working basis of the engagement; where project information issued after appointment materially differs, the affected term is adjusted by agreement before additional cost is incurred.

1. Authoring boundary. The role is management, coordination and verification only. No discipline model, including the LOD 400 record model, is authored by the BIM Manager; the record model is produced by the design consultants from contractor as-built documentation per A1 Deliverable D and verified under this engagement.

2. LOD framework. LOD applies per the Owner's definitions, in which LOD 400 constitutes as-built information, implemented through the unified matrix in Section 3.5. The Owner's BIM modeling standards are adopted in full upon issue and take precedence over interim ISO 19650 conventions.

3. Software and hardware. The BIM Manager's seats (AEC Collection, ACC BIM Collaborate Pro, Bluebeam Revu) are included at cost per Section 6, and the BIMBox class workstation in Section 3.7 is provided at no cost to the project. Every other firm provides its own authoring licences, ACC seats and hardware.

4. Programme basis. Phase 2 is priced at 8 months per the invitation and Phase 3 at 32 months, with extension handled automatically at the monthly rates in Section 6.1; programme risk is carried through this mechanism rather than through contingency in the base fee.

5. Model count. Coordination covers the model breakdown in Section 3.6, up to ten concurrent models including contractor and design-build models during construction. A materially larger model set is a change.

6. Defects liability period. The DLP is covered by the fixed close-out fee for Deliverable D verification. Recurring services through the 12 month DLP, if requested, are charged at the hourly rate.

7. Input dependency. Consultants publish native Revit 2025 models on shared coordinates per the exchange calendar. Re-coordination caused by late design changes after Deliverable C sign-off, beyond two additional clash cycles, is an additional service.

8. Site presence. Up to two site visits per month during construction are included; the consultant is Kampala based so visits carry no travel premium. Standing full time site presence would require a revised Phase 3 rate.

9. Insurance. No professional indemnity insurance is included in the fee. Should the Owner or Symbion require specified PI cover, it will be arranged and charged at documented premium cost.

10. Intellectual property. Models and project information are the Owner's property per A1, including submission to the Owner's catalog at Deliverable D. The consultant retains ownership of pre-existing tools, templates and know-how and grants a licence for their project output.

11. Currency. Fees are in USD; payment in Uganda shillings converts at the Bank of Uganda mid-rate on the invoice date.

12. Contract form. Engagement is as sub-consultant to Symbion under a simple consultancy agreement. Payment to the BIM Manager is not conditional on Symbion's receipt of payment from the Owner. Either party may terminate on 60 days written notice, with fees payable to the termination date plus committed software costs.

8. Acceptance

This proposal is open for acceptance for 30 days from 11 June 2026, by signed copy of this document or by issue of a sub-consultancy agreement consistent with Sections 6 and 7, whichever is earlier. Mobilisation commences within five working days of appointment.

For the Consultant:

Name: Mayanja Davis, BIM/CAD Specialist

Signature: 

Date: 12th June 2026

For Symbion Consulting Group Studios:

Name: _____

Signature: _____ Date: _____